SAVANNAH TANK
AND EQUIPMENT CORPORATION

1517 Telfair Road
Savannah, GA 31415
(912) 233-8902

To: **Valmet** Date: **6/12/25**

ATTN: **Ron Reed** Quote # **9211.1**

ITEM	QTY	DESCRIPTION	PRICE
1	**(1)**	**Dissolving Tank – 2205 Duplex** **Per Drawing MF00888716** **And the following:**	**$835,000.00**

Material: Duplex 2205 Stainless on all wetted parts
240-304/304L SS for non-wetted parts
Carbon steel for non-wetted structural supports

Finish: All welds to be free of slag, burrs, and rough edges
Interior and exterior stainless components will be cleaned and passivated

Carbon steel components to be blasted and painted with (2) coats of Sherwin Williams Macropoxy 646 epoxy 5 mils each, for total of at least 10 mils

Tank Design: Designed and fabricated per customer drawing and specifications

Tank Dimensions: 20' x 42' oval x 12' tall; shell to be 1/2" thick reinforced by carbon steel stiffeners. Tank to be fully assembled in shop for customer inspection prior to disassembly and shipment.

Top Head Style: 1/2" thick flat roof, reinforced with carbon steel stiffeners.
Includes (5) collar openings as shown on customer drawing.

Bottom Head Style: 1/2" thick flat

Supports: (8) Anchor plates w/ gussets

Baffles: None included

Nozzles: (3) 1" 3000# Couplings
(10) 1" 150# RFSO flanges
(5) 3" 150# RFSO flanges
(1) 8" 150# RFSO flange
(2) 10" RFSO flanges
(3) 12" RFSO flanges
(1) Valmet standard overflow
(3) Agitator wall rings (supplied by others; installed by ST&E)
(1) 40" x 72" access door
(2) ~60" stack connections (location to be etched in plate; cut out in field by others)
(5) Spout Collars (Supplied & installed by others; location to be etched in plate; cut out in field by others)

1517 Telfair Road
Savannah, GA 31415
(912) 233-8902

Insulation Rings: None included

Notes/ Exceptions:

No pressure test included.

Tank to be assembled in shop, then split into 2 halves for delivery. Sections to be match-marked for re-assembly in field and beveled for field welding.

Vacuum box testing included on roof and floor plate butt welds

10% RT included on all shell plate butt welds; 100% RT can be added for $25,500.00

Dye-Pen included for on all nozzle welds and 10% of other attachments

All welds to be visually inspected

Final assembly and field welding by others.

Savannah Tank reserves the right to weld using GTAW, GMAW, SMAW, FCAW, and SAW processes in the fabrication of this equipment.

All valves, gauges, and instrumentation by others

All blinds provided with B7 bolting and non-asbestos test gaskets. Service gaskets by others.

No nozzle loadings included unless specifically requested

Corrosion allowance if any specified only applied to heads and shells unless specifically requested

Quote assumes Savannah Tank standard internal nozzle projection of 1" (with exception to drain nozzles) unless specifically requested otherwise

Quote assumes Savannah Tank standard on internal components (i.e. baffles, dip pipe supports, and coil supports)

Quote assumes Savannah Tank standard on External components (i.e. lift lugs, vessel supports, and insulation rings)

Quote assumes Savannah Tank may use any fit-up, fabrication, or welding process that conforms to applicable codes

1517 Telfair Road
Savannah, GA 31415
(912) 233-8902

	DESCRIPTION	PRICE
	Freight is FOB our facility	**TBD**
	**Note: Freight estimate subject to change based upon final design of equipment and number/size of pieces shipped*	

PAYMENT TERMS:

10% upon completion of approval prints
50% upon receipt of major raw materials at Savannah Tank
40% balance upon tank completion

**Note: All terms are Net 30 days*

DELIVERY SCHEDULE:

Allow 3-4 weeks for submittal of initial approval drawings.
The drawing approval process will confirm nozzle locations and sizes.

Allow 20-24 weeks **AFTER RETURN** of "APPROVED FOR FABRICATION" drawings for completion of fabrication.

**Note: Schedules are based on tank dimensions, material type, and pressure rating detailed on this quote. It is Savannah Tank's standard to purchase major materials at time of order, prior to approval of the tank fabrication drawings. Changes made during the drawing approval stage that affect the tank design and/or dimensions could result in unused material being added to the scope of the job and tank price. It is the responsibility of the customer to notify Savannah Tank If major materials cannot be purchased at time of order. In doing so, the above delivery schedule is no longer accurate and all additional costs from possible material increases from time of quote to eventual order of material will be billed to the customer.*

NOTES:

SAVANNAH TANK AND EQUIPMENT, CORP. PROPOSES TO FURNISH THE EQUIPMENT SPECIFIED HEREIN AT THE PRICES STATED AND IN ACCORDANCE WITH THE TERMS, AND CONDITIONS STATED HEREIN AND ON THE REVERSE SIDE HEREOF AND ALL ATTACHMENTS.

Savannah Tank is not responsible for compatibility between material of the tank and the liquid product, based on the potential product variety, concentration, & tank cleaning chemistry being outside our control.

Gasket type, if any, called out in this proposal is an indication of what has been included in quoted pricing. Final gasket requirements are to be confirmed or specified by customer during drawing approval process and may require additional charges.

PRICE & DELIVERY ARE SUBJECT TO CHANGE DUE TO PRODUCTION VOLUME & MATERIALS PRICING / AVAILABILITY. **DUE TO VOLATILITY IN STEEL SUPPLY, PRICING AND DELIVERY SUBJECT TO CHANGE BASED ON CONFIRMATION FROM MILL AT TIME OF MATERIAL SHIPMENT.**

Thank you for the opportunity

THIS PROPOSAL IS MADE SUBJECT TO ACCEPTANCE BY THE DATE SHOWN ABOVE.
THE PRICES QUOTED DO NOT INCLUDE SALES, USE, EXCISE, OR OTHER GOVERNMENTAL CHARGES WHICH ARE TO BE PAID BY THE PURCHASER UNLESS THE PURCHASER PROVIDES SAVANNAH TANK & EQUIPMENT CORP. WITH A TAX-EXEMPT CERTIFICATE ACCEPTABLE TO THE TAXING AUTHORITIES.

RESPECTFULLY SUBMITTED

Chris Fletcher / Sales & Estimating Manager
chris.fletcher@savannahtank.com
office: 912-233-8902 ext. 103